

# AKASH ENCLAVE APARTMENT OWNERS' WELFARE AND MAINTENANCE ASSOCIATION

Ground Floor, Society Club Office, Akash Enclave, Sector 6A, Vrindavan Yojana, Rao Bareilly Road, Lucknow - 226029. (UP)

Reg : 418 - 2014 / File No. 1-173686

Rajeev Sharma, IAS (Retd.)  
President  
☎ 9452577194

Om Narain Dixit  
Vice President  
☎ 9839036995

Dr. Mrityunjai Kumar Singh  
Secretary  
☎ 9560959421

Sunil Kumar Kushwaha  
Treasurer  
☎ 8172884888

Ref.: 120/AE/2025-26

## QUOTATION NOTICE


Date : 16/04/2025

Sealed Quotation are invited by the undersigned for the Boring work at Akash Enclave Campus, Sector-6, Vrindavan Yojna, Lucknow as detailed given below. Quotation shall be received at Akash Enclave Society office, Lucknow upto 3.00 PM on 17 Apr 2025 and shall be opened on the same day at 3.30 pm.

Sl. No.	ITEMS OF WORK	Qty.	Unit	Rate in Rs.
1	4" PVC casing pipe of Finolex / Supreme make	33	length	
2	4" PVC casing pipe Ribbed screen. Finolex / Supreme	07	length	
3	4" PVC end cap Finolex / Supreme make.	01	No	
4	Coarse sand for screening of well	100	Cu ft	
5	Submersible pump of KSB make, 2HP.	01	set	
6	2.5 Sqmm sumersible cable (Finolex / KSB make)	90	Mtr	
7	Starter for pump L&T make	01	No	
8	Wire rope Heavy duty	80	Mtr	
9	32 mm PVC column pipe. (Astral make Heavy duty)	25	Length	
10	32 mm CI adapter for pump	01	set	
11	32 mm MS patia clamp	01	set	
12	PVC Bor cap	01	No	
13	32 x 25 mm GI Elbow	01	No	
14	25x150 mm GI nipple	01	No	
15	40 x 32 mm MS bush	01	No	
16	300 mm heavy PVC pipe for casing of Bor hole	10	ft	
17	Polytheen sheet for mud pit	01	No	
18	Nylon Mesh for cover the outer surface of 4" PVC ribbed	22	Mtr	
19	Bentonite powder (40 kg)	05	bag	
20	Transportation of Drilling Rig machine	01	Job	
21	Digging of pit for water circulation	01	Job	
22	Digging of 10" dia bor hole for lowring of 4" dia PVC pipe	400	Feet	

### Terms and Conditions:-

1. All works shall be carried out as per direction of UP Jal Nigam / PWD specification and Board of Members.
2. Work shall be completed within 15 days.
3. Payment should be done after discharge of clear water from boring and satisfactory completion of the work with site clearance.
4. Any extra Work which will be executed at site and not included in above SI No. 1 to 22 will be paid extra as per market rate.

  
President  
Akash Enclave