



RR Solar Power Solutions

Raghavendra Enterprises

GSTN: 29AMDPR5331G1ZY

Address: 4th Floor, Padma Complex, beside DCC bank, Hyderabad road, Bidar.

Mob: +91-7676659083, 9448038803

# OSWAL SMART SOLAR KIT

## One-Stop Solar Solution for Quick Installation



Avail Subsidy benefit up to 78000 with PM Surya Ghar Muft Bijli Yojana




## PRICE LIST MARCH 2026 (EXC. FREIGHT)

Sr. No.	Capacity	PV-Module Quantity	Basic Price	GST Rate	Tax Amount	GST Included Price
1	2KW , Mono Bi-Facial (DCR) SP	550*4	1,27,906	5.00%	6395	₹ 1,34,301
2	3KW , Mono Bi-Facial (DCR) SP	550*6	1,67,261	5.00%	8363	₹ 1,75,625
3	5KW , Mono Bi-Facial (DCR) SP	550*9	2,31,773	5.00%	11588	₹ 2,43,362
4	5KW , Mono Bi-Facial (DCR) TP	550*9	2,65,039	5.00%	13252	₹ 2,78,290
5	6KW , Mono Bi-Facial (DCR) TP	550*11	3,04,069	5.00%	15203	₹ 3,19,572
6	8KW , Mono Bi-Facial (DCR) TP	550*15	3,78,248	5.00%	18912	₹ 3,97,160
7	10KW , Mono Bi-Facial (DCR) TP	550*18	4,32,910	5.00%	21645	₹ 4,54,546

**Terms and conditions\*\***

Price is valid for **ONE MONTH**



## 2KW SP ON-GRID (DCR) SPG SMART SOLAR KIT

Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono perc half-cut, Bi-facial M10 550W (DCR)	04	Pcs
2	Inverter	OSS-201SP 2Kw MPPT based, grid-tie Inverter	01	Pcs
3	DCDB	1IN 1OUT with 600V DC SPD, 32A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	320V AC SPD & 32A MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4Sq.mm, copper XLPO, DC-Cable	25	Meter
6	Earth Rod	Copper bonded electrode, 14 mm Dia, 1-meter long	03	Pcs
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C, 4Sq.mm copper flexible green cable	100	Meter
9	Earthing Cable	1C, 6Sq.mm copper flexible (Y+G) cable	33	Meter
10	Kit Packing Box	Earthing box & BOS kit box	02	Pcs

### Terms and Conditions\*\*

- Price valid for the month of **ONE MONTH**, It can be change according to market fluctuations.
- Mentioned BOM consist of 9 different products including PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.
- Transportation excluded.



### 3KW SP ON-GRID (DCR) SPG SMART SOLAR KIT

Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono perc half-cut, Bi-facial M10 550W (DCR)	6	Pcs
2	Inverter	OSS-301SP 3Kw MPPT based, grid-tie Inverter	1	Pcs
3	DCDB	1IN 1OUT with 600V DC SPD, 32A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	320V AC SPD & 32A MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4Sq.mm, copper XLPO, DC-Cable	33	Meter
6	Earthing Rod	Copper bonded electrode, 14 mm Dia, 1-meter long	03	Pcs
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C, 4Sq.mm copper flexible green cable	100	Meter
9	Earthing Cable	1C, 6Sq.mm copper flexible (Y+G) cable	33	Meter
10	Kit Packing Box	Earthing box & BOS kit box	02	Pcs

**Terms and Conditions\*\***

- Price valid for the month of **ONE MONTH**. It can be change according to market fluctuations.
- Mentioned BOM consist of 9 different products including PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.
- Transportation excluded.



## 5KW SP ON-GRID (DCR) SPG SMART SOLAR KIT

Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono perc half-cut, Bi-facial M10 550W (DCR)	9	Pcs
2	Inverter	OSS-502SP 5Kw MPPT based, grid-tie Inverter	1	Pcs
3	DCDB	1IN 1OUT with 600V DC SPD, 32A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	320V AC SPD & 32A MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4Sq.mm, copper XLPO, DC-Cable	50	Meter
6	Earthing Rod	Copper bonded electrode, 14 mm Dia, 1-meter long	03	Pcs
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C, 4Sq.mm copper flexible green cable	100	Meter
9	Earthing Cable	1C, 6Sq.mm copper flexible (Y+G) cable	33	Meter
10	Kit Packing Box	Earthing box & BOS kit box	02	Pcs

**Terms and Conditions\*\***

- Price valid for the month of **ONE MONTH**. It can be change according to market fluctuations.
- Mentioned BOM consist of 9 different products including PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.
- Transportation excluded.



## 5KW TP ON-GRID (DCR) SPG SMART SOLAR KIT


Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono Perc half-cut, Bi-facial M10 550W (DCR)	9	Pcs
2	Inverter	OSS-502TP 5Kw MPPT based, grid-tie Inverter	1	Pcs
3	DCDB	2IN 2OUT with 600V DC SPD type-2 , 25A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	4P AC SPD type-2 & 25A 2-pole MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4 Sq.mm, copper XLPO, DC-Cable	50	Meter
6	Earthing Rod	Copper bonded electrode, 14mm dia, 1-meter long	03	Pcs.
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C 6 Sq.mm, copper flexible (Y+G) cable	100	Meter
9	Kit Packing Box	Earthing box & BOS kit box	02	Pcs

Transportation Terms and Conditions\*\*

Price valid for the month of **ONE MONTH**, It can be change according to market fluctuations.

Mentioned BOM consist of 8 different products including PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.

Transportation excluded.




## 6KW TP ON-GRID (DCR) SPG SMART SOLAR KIT

Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono Perc half-cut, Bi-facial M10 550W (DCR)	11	Pcs
2	Inverter	OSS-602TP 6Kw MPPT based, grid-tie Inverter	1	Pcs
3	DCDB	2IN 2OUT with 600V DC SPD type-2 , 25A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	4P AC SPD type-2 & 25A 2-pole MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4 Sq.mm, copper XLPO, DC-Cable	60	Meter
6	Earthing Rod	Copper bonded electrode, 14mm dia, 1-meter long	03	Pcs
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C 6 Sq.mm, copper flexible (Y+G) cable	100	Meter
9	Kit Packing Box	Earthing box & BOS kit box	02	Pcs

### Terms and Conditions\*\*

- Price valid for the month of **ONE MONTH**; It can be change according to market fluctuations.
- Mentioned BOM consist of **8** different products including **PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.**
- Transportation excluded.




## 8KW TP ON-GRID (DCR) SPG SMART SOLAR KIT

Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono Perc half-cut, Bi-facial M10 550W (DCR)	15	Pcs
2	Inverter	OSS-082TP 8Kw MPPT based, grid-tie Inverter	1	Pcs
3	DCDB	2IN 2OUT with 1000V DC SPD type-2 , 25A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	4P AC SPD type-2 & 25A 2-pole MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4 Sq.mm, copper XLPO, DC-Cable	80	Meter
6	Earthing Rod	Copper bonded electrode, 14mm dia, 1-meter long	03	Pcs
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C 6 Sq.mm, copper flexible (Y+G) cable	100	Meter
p	Packing Box	Earthing box & BOS kit box	02	Pcs

### Terms and Conditions\*\*

- Price valid for the month of **ONE MONTH** ; It can be change according to market fluctuations.
- Mentioned BOM consist of **8** different products including PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.
- Transportation excluded.



## 10KW TP ON-GRID (DCR) SPG SMART SOLAR KIT

Sr. No.	Component	Specification	Quantity	UOM
1	Solar PV-Module	Mono Perc half-cut, Bi-facial M10 550W (DCR)	18	Pcs
2	Inverter	OSS-102TP 10Kw MPPT based, grid-tie Inverter	1	Pcs
3	DCDB	2IN 2OUT with 1000V DC SPD type-2 , 25A fuses & PC enclosure of IP65 protection	01	Pcs
4	ACDB	4P AC SPD type-2 & 25A 2-pole MCB with IP-65 enclosure	01	Pcs
5	DC-Cable	4 Sq.mm, copper XLPO, DC-Cable	100	Meter
6	Earthing Rod	Copper bonded electrode, 14mm dia, 1-meter long	03	Pcs
7	Lightening Arrestor	Conventional type copper bonded, 1-meter long	01	Pcs
8	Earthing Cable	1C 6 Sq.mm, copper flexible (Y+G) cable	100	Meter
9	Packing Box	Earthing box & BOS kit box	02	Pcs

### Terms and Conditions\*\*

- Price valid for the month of **ONE MONTH** , It can be change according to market fluctuations.
- Mentioned BOM consist of 8 different products including PV-Module, Inverter, ACDB, DCDB, DC Cables, Earthing Cable, Earthing Kit, Etc.
- Transportation excluded.