

Category	Items/Services to Procure or Implement	Quantity/Details
Welfare Facilities	Portable toilets	Minimum 2 units
	Washing stations with hot and cold water	Minimum 2 units
	Soap dispensers	2 units per washing station
	Rest area with seating and tables	1 setup for 10 workers
	Microwave and refrigerator for meal preparation	1 of each
	Drinking water dispenser	Minimum 1 unit
	Regular cleaning services	Weekly or as required
Signage	Warning signs: "Danger", "Construction Site No Unauthorized Access"	Minimum 5 for site perimeter
	Fire safety signs: "Fire Extinguisher", "Fire Exit", "Assembly Point"	Minimum 2 per relevant zone
	PPE requirement signs: "Hard Hat Area", "Safety Boots Required"	Minimum 2



	Directional signs: "First Aid", "Rest Area", "Office"	Minimum 2 per zone
	Excavation warning signs	1 per excavation area
	Scaffolding inspection tags	1 per scaffold structure
Personal Protective Equipment (PPE)	Hard hats	For all workers + 10% reserve
	High-visibility vests	For all workers + 10% reserve
	safety shoes	For all workers + 10% reserve
	Gloves (cut-resistant and general-purpose)	2 pairs per worker
	Safety goggles	For all workers + 10% reserve
	Dust masks or respirators (with RPE testing)	For all workers
	Ear defenders (if required based on noise levels)	For noise-exposed workers + 10% reserve
Dust Control Equipment	Water spraying systems	Minimum 2 units



Fire Safety Equipment	Fire extinguishers (ABC type)	Minimum 2 per zone
	Fire blankets	Minimum 2
	Waste bins (for safe waste disposal)	1 per relevant area
Work at Height	Scaffolding compliant with NASC TG20 standards	As per site requirements
	Safety nets and guardrails	For all open edges
	Fall arrest systems (harnesses and lanyards)	For workers at risk of falling
Excavation Safety	Shoring equipment or trench boxes	For all excavation areas
	Safety barriers	As needed for excavation perimeter
	Warning tape or fencing	Minimum 50 meters
Demolition Work	Structural survey services	1 service
	Temporary works design services	1 service



	Heavy machinery for controlled demolition (e.g., excavators, cranes)	Based on demolition plan
Training Services	Toolbox talks on site-specific risks	Weekly sessions
	Manual handling training	For all workers
	PPE usage and RPE face-fit testing	For all workers
	Fire safety training	For all workers
Temporary Works	Temporary works supervisor services	1 qualified supervisor
	Temporary works design calculations	As per structure requirements
	Propping and support equipment	Based on site assessment